

Name of work :- Refurbishment and Renovations of Hi-Tech Orchidarium and Mist Chamber, Landscaping and beautification of Assam Bio-Resource Centre at Madam Kamdev.

TENDER PAPER

(Contractor's are requested to quote the rates against each items with duly signed and seal in each pages)

Sl. No.	Descriptions Of Items	Unit	Quantity	Rate (In Rs.)	Amount (In Rs.)
1	2	3	4	5	6
1	Dismantling Polycarbonate sheet or other hard board or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead	SQM	350.13	₹	₹
2	Painting with synthetic enamel paint of approved brand and manufacture With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel worksure of required colour to give an even shade	SQM	281.83	₹	₹
3	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete.				
	On steel work	SQM	281.83	₹	₹
4	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge.				
	Made of G.I. wire of dia. 4 mm, PVC coated to achieve outer dia not less than 5 mm in required colour and shadeire of dia 4 mm	SQM	324.93	₹	₹

5	Providing and fixing Agro Shed of required 70% shading as required complete as per the direction of Engineer-in-charge.	SQM	275.20	₹	₹
6	Supplying, fitting and fixing of 1.50 H.P Pump and removal of existing sprinkler at Assam Bio-Resource Centre at Madan Kemdev.	No.	1.00	₹	₹
7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work				
	20 mm nominal dia Pipes	RM	20.00	₹	₹
8	25 mm nominal dia Pipes metre	RM	25.00	₹	₹
9	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	CUM	3.60	₹	₹
10	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :				
	Cement mortar 1:3 (1 cement : 3 coarse sand)	SQM	32.00	₹	₹

11	Dry brick on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with Jamuna sand, with common burnt clay non modular bricks.	SQM	40.00	₹	₹
Landscaping and beautifications					
12	Carpet Grass	Sqft.	2450.00	₹	₹
13	Sijium	Job.	100.00	₹	₹
14	Kamie Daware	Job.	100.00	₹	₹
15	Pandanus Pygmi	Job.	200.00	₹	₹
16	Ficus Big	Job.	5.00	₹	₹
17	Exora	Job.	100.00	₹	₹
18	Ficus	Job.	50.00	₹	₹
TOTAL AMOUNT				₹	
(Total amount in words)					

Contractor's signature
with Seal